BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 19th October 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 12th November 1938, for the work of constructing drains in Chikmagalur Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,075 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of constructing drains in Chikmagalur Town," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Director of Public Health in Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Public Health will be final and legally binding.

Estimate of the approximate quantities for constructing drains in Chikmagalur Town.

No.	Items of work	Unit	Quantity
1	Constructing 3" section semi-peg top section drains with cement concrete in the proportion of 1 : 2 : 4 and plastering the surface with ½" cement mortar in the proportion of 1 : 3 including earthwork as per type design	R.ft.	1,915
2	Constructing silk pattern drains with old slabs including removing, resetting and dressing and conveying with 1½" thick cement concrete in the proportion of 1 : 2 : 4 over 3" surki burnt stone jelly concrete bed and surface plastered with ½" cement mortar and earthwork excavation, etc., complete as per design. 3" section	R.ft.	315
3	Do do with 3" to 4" thick new burnt stone slab cheeks, 1½" thick cement concrete on 3" thick surki concrete bed and the surface plastered with ½" cement mortar and earthwork, etc., complete as per design .. 3" section	R.ft.	2,073
4	Do do .. 4" (1) Section	,,	500
5	Do do .. 4" (2) Section	,,	995
6	Do do .. 5" (2) Section	,,	1,015
7	Do do .. 6" (3) Section	,,	515
8	Do do .. 7" (2) Section	,,	400

N. KRISHNIENGAR,
Sanitary Engineer.